

Eagle Road Improvement Project

Adding continuous raised medians

Continuous raised medians will control access to and from the roadway, but more importantly, will reduce accidents and improve safety along Eagle Road.

Continuous raised medians will be built along Eagle Road between Franklin Road and State Street. The medians are designed to be six inches high and range from two to 13 feet wide. The medians will be made of concrete.

